

Lumpkin County Fire / EMS

57 A Pinetree Way
Dahlonega Ga. 30533

Edward Eggert
Fire Chief

Effective January 06, 2006

Project Check List

Below are some items that will be required while the building process takes place.

1. A water main with hydrants spacing as necessary to facilitate a 300' lay of fire hose to any portion of all buildings. This distance is measured 'as the truck travels'. All fire hydrants shall be capable of providing a minimum flow of 1250 gallons per minute.
2. Hydrants and mains shall be installed and under pressure **before** any combustible construction is started.
3. Certification and flow tests shall be provided to the fire department after installation of the water mains.
4. Every building hereafter constructed shall be accessible to fire department vehicles.
5. Maintain access for emergency vehicles around and to all buildings under construction. i.e.: In times of rain or mud, roads shall be capable of carrying the weight of a fire truck by being paved or having a crushed stone base etc. This emergency access shall be a minimum of 20 feet wide (International Fire Code 2003).

All burning of land clearing debris must be done according to Georgia Forestry Commission, Georgia EPD, and/or City of Dahlonega regulations.

